



Figure 12 - Likelihood of area containing Aboriginal cultural heritage

Development of the southern part of the precinct is likely to occur first and therefore require the first servicing. Ahead of the new main to the Riverstone carrier, this land may require an interim servicing solution with details yet to be determined.

SPS 'B'

Flows within this catchment could be transferred by gravity to a future pumping station, SPS 'B'. As a result of the current planning position and associated funding routes, Sydney Water has advised that it has no committed timeframe for delivery of this pumping station and would unlikely be constructed before 2024 at the earliest, subject to funding.



Figure 9 - Wastewater catchments